



DEENDAYAL PORT AUTHORITY



SAGARMALA
PORT



Office of the Executive Engineer (TD),
Room No.125, Annexe,
Administrative Office,
Gandhidham – Kutch, Pin – 370 201
E – Mail: tddivisionkpt@gmail.com

No :- TW/WK/7858/11988

Date:24/05/2024

To,

Expression of Interest.

Sub: - S/R to Sports Complex at Port Colony Gopalpuri, Gandhidham.

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department for a period of six months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of Interest along with budgetary offer for the above work should reach to the following address on or before 31/05/2024 by 15:00 Hrs.

Address:-

Office of the Executive Engineer (TD),
T.D. Division, Administrative Office Building,
Ground floor, Room No.105, Annexe,
P.O. Box No. 50, Gandhidham – Kachchh.
Email: tddivisionkpt@gmail.com

Thanking you,

Yours faithfully,


Executive Engineer (TD)
Deendayal Port Authority

Annexure-I					
Item No.	DESCRIPTION	Total Qty.	UNIT	RATE (In ₹.)	AMOUNT (In ₹)
PART - A Execution					
1	Football Ground				
(i)	Refurbishment of the base etc. for Installation of synthetic artificial turf for a football field from a FIFA preferred provider as per tender.	9690.00	M2		
(ii)	Supply and Installation of synthetic artificial turf for a football field from a FIFA preferred provider having finger unit coating permeable backing, pile height 50mm, polyethylene slit filament, fire retardant, certified lead free, including customs clearance, insurance, infill comprising of rubber (0.85 kg/sft) and silica sand (2.4kg/sft). The proposed brand needs to be from America/Europe/Australia origin only. The agency also needs to provide unloading and staging of rolls, sewing of seams, infilling with appropriate dispensing, spreading and levelling equipment, brushing of fibres with all poly-hydraulic controlled equipment as directed by Engineer in charge.	9690.00	M2		
2	Athletic Track				
(i)	Refurbishment of the base etc. for Installation of synthetic athletic track all complete as per requirements/specifications laid down by World Athletics (IAAF) preferred provider including UV Seal Coating.	3200.00	M2		
(ii)	Supply and Installation of synthetic athletic track including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) from a firm who had previously supplied and installed the original cast in-situ athletic track.	3200.00	M2		
PART - B Credit item to DPA					
3	Removal of existing football turf, Surface dressing of the ground including removing and disposal of same & transportation. The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge.	9690.00	M2		
4	Removal of existing synthetic athletic track, Surface dressing including removing and disposal of same & transportation at local body location approved. The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge.	3200.00	M2		