

CONSTRUCTION - I DIVISION

**Name of Work: PROVIDING COMMON APPROACH ROAD CONNECTIVITY FOR PROPOSED
GREEN HYDROGEN PLOTS AT PADANA (PHASE-I)**

Sr.No.	Description	QTY	Unit	Rate
5	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with truck in first layer of 1mt from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.	300000.00	m3	
6	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with road roller 8 to 10 t capacity for remaining layers to achive the omc from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge	1476750.00	m3	