

DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (H),
Nirmar Building,
Kandla-Kachchh
www.deendayalport.gov.in

No: HW/WK/

Date: 23/07/2024

To,

Expression of Interest.

Sub: - Development of area for R&D yard beyond chainage 14/0 Km to facilitate upcoming new projects at Tekra.

Sir,

Deendayal Port Authority intends to carry out the subject work of Harbour Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary – offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary quotation for the above work should be submitted through email to the id: kphdivision@gmail.com or hard copy to the following address on or before 30/07/2024 by 18:00 Hrs.

Address: -

Office of the Executive Engineer (H),
Harbour Division, 1st floor,
Nirmar Building, – Kachchh (370201)

Thanking you,

Yours faithfully,

Executive Engineer (H)
Deendayal Port Authority

BUDGETARY OFFER

Sr. No.	Description	Unit	Rate
1.	Supplying of Biaxial Geo-grid, made from virgin high density polypropylene, having aperture size of 65mmx 65mm and ultimate tensile strength of 40 kN/m with minimum junction efficiency of 95% & minimum radial stiffness of 400 kN/m (@0.5% strain including cost of material and transportation up to Tuna.	M2	
2	Stone Aggregate (Single size) : 50 mm nominal size including Carriage upto Tuna	M3	
3	Stone aggregate 40 mm nominal size and above including carried up to Tuna	M3	
4	Stone aggregate 20 mm nominal size and above including carried up to Tuna	M3	
5	Stone Aggregate (Single size) : 10 mm nominal size including carried up to Tuna	M3	
6	Crushed stone 2.36 mm to 12.5 mm size including carried up to Tuna	M3	
7	Stone chippings/ screenings 4.75 mm nominal size including carried up to Tuna	M3	
8	Stone chippings/ screenings 150 micron including carried up to Tuna	M3	
9	Supplying of Quarry spall material (Having CBR value more than 20) including cost of material, excavation, royalty, loading, unloading, Transportation to Tuna.	M3	