


DEENDAYAL PORT AUTHORITY

ISO 9001-2015 & ISO 14001-2015




75
आजादी का
अमृत महोत्सव

SAGARMALA
PORT LED PROSPERITY



SIPC
KANDLA
RIDE THE WAVE OF PROGRESS



Office of The Executive Engineer (TD)
Town Development Division
Room No. 105, ANNEXE,
Administrative Office Building,
Gandhidham – Kutch Pin – 370 201
E – Mail: tddivisionkpt@gmail.com
Website: www.deendayalport.gov.in

No.TW/WK/ 788/1 EOI 11881

Date : 22/07/2024

To,

-----,
-----,
-----,

EXPRESSION OF INTEREST

Sub: Construction of E-Type Quarters at Port Colony Gopalpuri, Gandhidham.

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department for the period of 18 Months.

Kindly submit your Expression of Interest (EOI) along with budgetary quotation offer for the subject work for the items considered for preparation of the Estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & Exclusive of GST. Applicable GST shall be shown separately, which shall not be considered for evaluation purpose.

Your Expression of Interest submit along with budgetary quotation for the above work should be reach to following address by Registered Post/Speed Post/ Courier on or before **29/07/2024 by 16:00 Hrs** .

Thanking you,

Yours faithfully,


Executive Engineer (TD)
Deendayal Port Authority

(on the letter head of Supplier/Bidder)

To,
Executive Engineer (TD Div.),
Room No. 105, A.O. Building
Deendayal Port Authority,
Gandhidham-Kutch-370201

Sub: Construction of E Quarters at Port Colony Gopalpuri

Annexure – “I”

Sr. No	Description	Unit	Rate(In Rs.)
1.	Providing of chicken wire mesh 150 mm wide 24 gauge with opening of 25x25mm including GI nails all complete.	M ²	
2.	Providing of mosquito aluminium Jali	Kg	
3.	Supplying of stainless-steel following fixtures with stainless steel screws, nut & bolts etc. complete.		
i.	Aldrops 300x16 mm Size	Each	
ii.	Aldrops 250x16 mm Size	Each	
iii.	Door Latch 250x16x5 mm Size	Each	
iv.	Handle 150 mm	Each	
v.	Handle 125 mm	Each	
vi.	Handle 100 mm	Each	
vii.	Tower Bolts 200 mm Size	Each	
viii.	Tower Bolts 100 mm Size	Each	
ix.	Floor door stopper with rubber cushion 150mm	Each	
x.	Towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face.	Each	
xi.	C.P. brass Health Faucet with 8mm dia 1.20m long Flexible tube and wall hook	Each	
xii.	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm complete with brackets fixed to wooden cleats with CP brass screws.	Each	

4.	Supplying of Aluminium Louvers for window/ventilator 500x600 MM in size complete with 4mm glass.	M ²	
5.	Supplying of Netlon Mosquito Net(Insect Screen)	M ²	
6.	Supplying of PVC manhole cover with Heavy duty with frame 600 x 600 mm x 5mm size	Each	
7.	Supplying of PVC soil waste pipe as per IS 4985 of following sizes:		
(i)	50mm dia pipe	RMT	
(ii)	75 mm Dia pipe	RMT	
(iii)	110 mm Dia pipe	RMT	
(iv)	160 mm dia pipe	RMT	
8.	Dismantling the existing Quarters including removing / separating out the salvage materials like doors & windows masonry, reinforcement etc. complete including removing the foundation and filling the unwanted material outside Gopalpuri upto 4 km lead, prepare the surface for reconstruction of the quarters as directed by the Engineer-in-charge .	M ²	
9.	Credit Item: Taking away the salvage material to be received from the dismantling of quarters, complete as directed by Engineer-in-charge.	M ²	

Seal & Signature of the Authorized Supplier