

No:

Dt: / / 2024.

Draft copy of quotation

To, _____

Name of Work :- Providing additional safety measures to VTMS building at Jetty , Vadinar.

Sealed quotation are invited from the intending contractors and piece workers for the following items up to 15:00 hrs on _____ date & the same will be opened by the Executive engineer © on the same day at 16:00 hrs.

No.	Description	Qty.	Rate	Unit	amt.
1	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Tubular door handle polyster powder coated ,100mm brass lock and stopper etc.all inclusive).	7.56	3663	m2	27,692.28
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM Rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed Mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (including 8mm th float glass glazing, panelling and dash fasteners etc.) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	93.74	3477.47	m2	3,25,978.04

No.	Description	Qty.	Rate	Unit	amt.
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture	34.76	98.04	m2	3,407.87
4	Filling the gap in between aluminium frame & adjacent RCC/ Brick/Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge. Up to 5mm depth and 5mm width	65.90	59.68	Rmt	3,932.91
5	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	200.66	113.79	m2	22,833.10

Total amount= 383844.20

I/we am/are agree to execute the work

at ____% above (In figure), _____% above(In words)

at ____% below (In figure), _____% below(In words)

Sign of Contractor

**Executive Engineer (C)
Deendayal Port Authority - OOT
Vadinar**