

Page-1  
**Construction Division**

Office of the Executive. Engineer (C),  
A.O. Building, Annexe,  
Room No. 129, Ground Floor  
Gandhidham (Kutch)

No. CN/WK/ CSR

Dated: /06/2024

To,

Sub:- CSR request for providing solar panel, Paver Block & city ride Vehicle at their hostel at Adipur - Kutch –  
**Paver Block flooring**

Sir,

Quotations are invited for the subject works to be carried out with terms and condition attached . Your quotation should reach this office latest by \_\_\_\_\_ at 15:00 hrs.

**SCHEDULE - B**

It. No.	Description of Item	Qty	Rate		Unit		Amount
			In Fig.	In Words	In Fig.	In Words	
1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	239.85			M2	One square meter	
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.						
A	Size of Tile 600x600 mm	16.5			M2	One square meter	
							Total Rs,

(Rs. In word \_\_\_\_\_)

**CONTRACTOR**

**Executive Engineer (C),  
Deendayal Port Authority**