

**Office of the Superintending Engineer,  
Harbour Division, Nirman Building,  
New Kandla (Kutch), Gujarat-370210.**



**Tel : (02836) 270325  
FAX : (02836) 270429**

**Email ID :-  
kphdivision@gmail.com**

ISO 9001:2008 ISO 14001:2004

No:HW/WK/EOI/

Dated : 26/09/2024

To,  
M/s .....

## **Expression of Interest**

Sub. : Up-gradation of Backup Area of Cargo Berth No. 15 & 16.

Sir,

Deendayal Port Trust intends to invite e-tender for the subject work.

Kindly submit your budgetary-offer for the subject work on the basis of tentative requirements of items execute for work enclosed herewith.

The rates quoted must be inclusive of all taxes, & exclusive of GST.

Your budgetary offer for the above work should reach to the above mentioned address on or before 07/10/2024.

Thanking you,

एक कदम स्वच्छता की ओर

Encl. : As above

Yours faithfully,

Executive Engineer (H)  
Deendayal Port Trust

**Date :-**

**To,  
The Executive Engineer (H)  
Deendayal Port Authority  
New Kandla**

**Sub. : Budgetary offer for the work of "Up-gradation of Backup Area of Cargo Berth No. 15 & 16".**

<b>Sr. No.</b>	<b>Item Description</b>	<b>Rate (in Rs.)</b>	<b>Qty</b>	<b>Unit</b>
1	<p>Providing &amp; Fixing Cable Tray support as per the <b>Technical Specification:</b> The FRP ladder type cable tray System shall be of following size: Width (W): 600mm Rung Width (W): 600mm Side Runner Height (H): 150mm Rung Width: <math>\geq 25</math> mm Rung Height: <math>\geq 25</math> mm Rung C to C: <math>\leq 250</math> mm Thickness (T): <math>\geq 4</math> mm Length (L): 3000mm/2500mm Thickness of Tray Cover: <math>\geq 2</math> mm</p> <p>The FRP material of the Cable Tray shall be Fire retardant, UV resistant, Halogen free, Non toxic, Non corrosive, Non erosive, Non magnetic and shall have high Load bearing capacity, very low thermal conductivity &amp; long life cycle.</p> <p>The Cable Tray System shall include all the accessories including but not limited to Horizontal Tee, 90 degree Elbow, etc. along with Coupler Plates, clamps, fasteners etc. (stainless steel SS304 material).</p> <p>The Cable Tray manufacturing shall be ISO 9001: 2000.</p> <p>The work includes loading unloading transportation and fixing on the RCC wall of the drain complete all material labour etc as directed.</p>		3000	RMT

Note : Rates shall be exclusive of GST