

Schedule B

Name of Work: Construction of Service Road From VillageJungi/vandhiya to village Veera for Demarcation and safe Guard of DPT land Bifurcating State Government land (Phase-)

Sr.No.	Description	QTY	Unit	Rate	Amount
1	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with truck in first layer of 500mm from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.	350000.00	m3		
2	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with road roller 8 to 10 t capacity for remaining layers to achive the omc from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.	1050000.00	m3		
3	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
	900mm dia	10400.00	RMT		
		Total			