

# DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (H),  
Nirmar Building,  
Kandla-Kachchh  
[www.deendayalport.gov.in](http://www.deendayalport.gov.in)

\*\*\*\*\*

No: HW/WK/

Date: 21/09/2024

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## Expression of Interest.

**Sub: - Two Years Contract for supply and maintenance of railway tracks inside and outside cargo jetty area (For Years 2025-27)..**

Sir,

Deendayal Port Authority intends to carry out the subject work of Harbour Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary – offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary quotation for the above work should be submitted through email to the id: [kphdivision@gmail.com](mailto:kphdivision@gmail.com) or hard copy to the following address on or before 28/09/2024 by 18:00 Hrs.

**Address: -**

Office of the Executive Engineer (H),  
Harbour Division, 1st floor,  
Nirmar Building, – Kachchh (370201)

Thanking you,

Yours faithfully,

Executive Engineer (H)  
Deendayal Port Authority

## Annexure-I

Name of work: Two Years Contract for supply and maintenance of railway tracks inside and outside cargo jetty area (For Years 2025-27).

Sr. No.	Description	Unit	Rate
1	Supply of Old / Used rails 60/52 kg 13.00 m long confirming to T-18 Industrial quality IRS specification suitable for check rail.	MT	
2	Supply and replacement of Special PSC sleeper for 60kg rail section as per RDSO drawing and as per IRS specification and Laying of special PSC sleeper for 60 Kg. rail section for fixing running rail OR Running rail and check rail as per requirement including removing of the old/damaged sleeper from its position and including shifting of sleepers upto any lead. (a) BG Track (PSC to PSC sleepers).	Each	
3	Supplying and Fixing of fish plate and fish bolt (of 4 fish bolts) as per RDSO T-2434 on a joint created in rail of 60Kg of all UTS, duly lubricating fish plate/bolts with contractor grease graphite.	Set	
4	Supplying and Fixing of fish plate 60Kg (1000mm long) and fish bolt (of 6 fish bolts) as per RDSO T-5916 on a joint created in rail of 60Kg of all UTS, duly lubricating fish plate/bolts with contractor grease graphite.	Set	
5	supplying and fixing Fish Bolts with Nuts of different sizes as per specifications etc. with all contractor's material, labour, tools & plants and machinery, drilling holes, all lead & lift etc. and as directed by the Engineer in-charge :		
	(a) Size 25mm x 130mm with nut & one plain washer to RDSO Drg. No. T-11501, conforming to latest IRS specification & alteration	Each	
6	Scattered replacement of Grooved Rubber Pads on PSC / ST sleepers, as directed by Engineer in-charge	Each	
7	Providing and fixing of New ERC clips while maintenance of open track or as and when required as per site condition as directed by Engineer-in-charge	Each	
8	Supplying & fixing in position metal Liners as per RDSO drawing no. T-3740	Each	
9	Dismantling of broad gauge railway lines and point and crossing with all fittings like sleepers, fishplates, fish nut bolts, dogspikes, canted bearingplates etc. loading, unloading sleepers, fishplates, fish nut bolts, dogspikes, canted bearingplates etc. loading, unloading transportation and stacking and sorting out unserviceable materials within lead of 1.2kms. Beyond 1.00 Km., including all labours required tools plants etc. complete as directed by Engineer-in-charge.	RMT	
10	Laying of 60 kg industrial quality as per IRS specification in Broad Gauge with two rails in track including cutting of rails, drilling of holes in rails and check rail joining connecting and fixing in line and level, placing and linking on prepared sub grade (formation) for BG track with 60 kg rail and PSC sleepers (1540 sleeper / km) with initial packing and fixing all relevant track filling i.e. Fish plates fish nuts & bolts, pendroll clips, GFN/Metal liners, resilient rubber pads etc. to the correct sleepers spacing, gauge alignment with all required tools & plants, all materials labours loading unloading transportation etc. complete as directed by Engineer in Charge. (Excluding supply of rails and sleepers).	Track Meter	
11	Replacement of damaged rail on wooden or PSC sleeper as per requirements (single rail of track) which includes removing of damaged rail from its position by removing necessary fish nut-bolts, fish plates, dog spikes/ rail screw/ pendroll clip, check rail brackets/ check blocks etc. and depositing the same in railway store and replacing by other rail, fixing of all relevant fittings like fish plates, fish nut-bolt, dog spikes/ plates screws, rubber pad, GFN/metal liner, pendroll clip etc. including with all loading, unloading and transportation etc. complete as directed by Engineer-in-charge. (Excluding the cost of rails and fittings)	RMT	

Note: Applicable GST to be paid extra