

दीनदयालपत्तनप्राधिकरण
DEENDAYAL PORT AUTHORITY
(Ministry of Ports, Shipping & Waterways, Govt. of India)
An ISO 9001 : 2015 & ISO 14001 : 2015 Certified Port

दूरभाष / Tel: 02836-233192
फैक्स / Fax: 02836-220050
e-mail: ce@deendayalport.gov.in
website: www.deendayalport.gov.in



मुख्य अभियंता का कार्यालय
Office of the Chief Engineer
उपभवन / Annex Building
Administrative Office, Post Box No. 50,
गांधीधाम (कच्छ)/Gandhidham (Kutch)

HW/WK/EOI/

Date: 13/11/2024

EXPRESSION OF INTEREST

To,
M/s

Sub.: - Construction of New Building for Workshop, time office & storage of machinery near SNA building.

Sir,

Deendayal Port Authority intends to invite e-tender for subject work.

Kindly submit your Expression of interest along with budgetary-offer for the subject work on the basis of tentative requirements of material enclosed herewith.

The rates quoted must be inclusive of all taxes, & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purpose.

Your Expression of interest along with budgetary offer for the above work should reach to the above mentioned address on or before 21/11/2024.

Yours faithfully,

Executive Engineer (H)
Deendayal Port Authority

To,
The Executive Engineer (H)
Deendayal Port Authority
New Kandla

Date :

Sub.- Construction of New Building for Workshop, time office & storage of machinery near SNA building.

Item No.	Description	Qty	Unit	Rate
1	Providing and fixing ISI marked flush door shutters conforming to IS :2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak and laminate with sunmica sheet 1mm thick on both faces of shutters.			
A	50 mm thick	41.04	m2	
2	Providing and laying Full body vitrified double charge floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades,laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand),jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.			
A	Size of Tile 600 x 600 mm (9 mm thick or as specified by manufacturer)			
1	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling /grouting and finishing complete as per direction of Engineer-in-charge.	978.30	m2	
3	Providing & fixing PVC Nahni trap 100 mm dia. with necessary fittings, making good the walls & floor, including cost of labour, materials etc., complete as directed.	10.00	Each	
4	Providing and fixing C.P .Brass Stop cock.			
A	15 mm dia. - weight 0.40 kg	10.00	Each	
5	Providing, laying & jointing PVC pipes of required working pressure as per I.S.I. 4985 including cutting and jointing the pipe ends as per manufacturer's instructions including the cost of specials wherever required and, excavation and refilling of the trenches or fixing on walls or similar structures with clamps and testing the joints etc. complete as directed.			
a	Pipe 75 mm outer dia. working pressure 4kg/cm2.	120.00	Mtr	
b	Pipe 160 mm outer dia. working pressure 6 kg/cm2.	100.00	Mtr	
6	Providing & fixing SWR PVC (I.S.I - IS 13592) waste or vent pipe including necessary specials such as Tees, Bends, Y's Plinth offsets, Shoes , Vent cowl etc . with bracket , screws on wooden plugs fixed on wall face including filling joints with solution & cement mortar 1:2 complete as directed.			
a	110 mm dia. (OD)	240.00	Mtr	

Item No.	Description	Qty	Unit	Rate
7	Supplying, testing, commissioning RO Plants of 150 Litre per hour capacity (including required PVC water tank) of approved make which consists of all necessary parts viz motor pump of required capacity, multipart valve, 20" bowl & filter silver process of high pressure pump of required capacity, multipart valve, 20" bowl & filter silver process of high pressure pump of required capacity, membrane, Rotameter, pressure meter, electric panel with M.S. Cabinet all necessary Electric & other connection required to commissioned the RO Plant which gives the required TDS complete with loading, unloading & Transportation, Installation including all taxes with one year warrantee and maintenance free.	1.00	Each	
8	Collection, and filling Black stone dust / Grit in foundation and trenches in a layer of av 20 cm including cost of Excavation ,Royalty, loading, unloading and transportation at the site of work.	3567.00	m3	
9	Collection and spreading of manure (goat dropping & cow dung dried) free from foreign materials subject to the approval of Engineer-in-Charge including loading, unloading, transport & stacking at site of work.	13.00	m3	
9	Collection and spreading of sweet earth including cost of excavation, royalty, loading, unloading, transport & stacking at site of work	268.00	m3	
10	supplying and fixing (Planting) green trees in said position including digging the soil for planting and providing necessary support to plant and wattering the plant till the completion of work and ansure the survival of plant till than.			
a	Different type of Palm, Coconut of 5 to 6 foot height above Ground Level	45.00	Each	
11	providing Furniture of various size and category like good quality office table as per requirment of various offices. The table shall be manufactured on site as per the requirment having one bigger drawer on both side of the table for storage of files and two smaller sliding drawer on both side of table (i.e. two bigger drawer and four smaller drawer in each table) and one sliding drawer for keeping key board at middel of table, all the drawer fixed with good quality telescopic channel, brass hinges, brass screw. Table shall be manufacture with good quality of 18 to19 mm thick gurjan ply ISI marked with hard wood framing if required (only bottom of drawer should be made of 8 mm gurgan ply ISI mrked) and all the area of table top, table bottom, table sides, inner and outer side of drawer, key board drawer etc should be finished with best quality of 1 mm thick laminate sunmica sheet, Computerized key & locks, handle and all other required fixtures complete as per the direction of Engineer-in-charge. (Note:- For payment purpose area of table top should be measured)	55.00	m2	

Item No.	Description	Qty	Unit	Rate
12	Providing and fixing of cupboard / side rack 60 cm in depth & 75 cm in height made with 18 to 19 mm thick gurgan ply at top, side, back and bottom & two sliding shutter & two sliding shelves (only bottom of sliding shelves should be made from 8 mm thick gurgan ply remaining all is of 19 mm thick gurgan ply) all side , top, bottom inside and outside should be laminate with 1.0 mm thick sunmica sheet, Computerized key & locks, handle and all other required fixtures including cost of all the labour, materials, nails, fevicols, screws, taxes etc. complete as directed by Engineer-in-charge. (Note:- For payment purpose lengh of rack should be measured)	71.00	m2	
13	providing & fixing of executive 360' revolving office chair with high back and ss body base with wheels & pneumatic up & down with one point locking mechanism + pu foam at seat and back ,fabric of make Godrej Interio, Neelkamal, Supreme, stylux. (Brand and type will be approved and as per direction of Engineer-in-charge.)	9.00	Each	
14	providing & fixing of visitor office chair with low back and with broad armrest and brake casters of make Godrej interio, neelkamal, supreme stylux. (Brand and type will be approved and as per direction of Engineer-in-charge.)	50.00	Each	
15	Providing & fixing of S.S. Staircase Railing Of 304Q grade with all required accessories for fixing . The pipes should be of 10 gauge thickness.The main railing pipe of 32 mm square box at 900 mm to 1200 mm c/c , with top railing of 50 mm dia and three lower horizontal railing pipe of 15 to 25 mm dia as directed. The height of railing is about 1.00 mtrs. The railing is to be provided as approved by the Engineer In Charge. The work includes all labour ,materials & tools/Plants etc.			
a	Matt / Glossy finish S S Railing	30.00	mtr	

GST will be paid extra.