

DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (H),
Nirmar Building,
Kandla-Kachchh
www.deendayalport.gov.in

Date: 04/11/2024

No: HW/WK/

To,

Expression of Interest.

Sub: - Two Years Contract for supply and maintenance of railway tracks inside and outside cargo jetty area (For Years 2025-27)..

Sir,

Deendayal Port Authority intends to carry out the subject work of Harbour Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary – offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary quotation for the above work should be submitted through email to the id: kphdivision@gmail.com or hard copy to the following address on or before 11/11/2024 by 18:00 Hrs.

Address: -

Office of the Executive Engineer (H),
Harbour Division, 1st floor,
Nirmar Building, – Kachchh (370201)

Thanking you,

Yours faithfully,

Executive Engineer (H)
Deendayal Port Authority



Annexure-I

Name of work: Two Years Contract for supply and maintenance of railway tracks inside and outside cargo jetty area (For Years 2025-27).

Sr. No.	Description	Unit	Rate
1	Manufacturing, supply and replacement of Railway's fragmented lifting barrier up to 10 m length at Non-interlocked LC (Manually operated) as per RDSO specifications and fixing it on supports, painting with two coats of synthetic enamel paints over one coat of red lead primer of approved quality & colour and setting lifting barrier for smooth operation complete and as directed.	Each	
2	Manufacturing, Supplying, Installation and commissioning of 6-10 M long non-interlocked lifting barriers on either side of road passing through the level crossing within Railway Limits with all accessories viz booms, fringes, boom loading device arrangement with its rod run and completed ground fitting, vertical wheel, diversion wheel, steel wire Rope with its accessories pedestals, trunion bracket, LB drum, mechanical warning bell arrangement, night light, three lever frame etc. complete including painting with flourescent paint, excavation & concreting of foundation. Note:- 1) All materials, equipment, labour, casting beds, stress frame, form work staging, scaffolding etc. is to be arranged by contractor within the quoted rates. 2) All design mix concrete shall be machine batched with automatic weight batcher, machine mixed and machine vibrated or ready mix concrete prepared in depot and transported by transit mixer to the site of work.	Set	

Note: Applicable GST to be paid extra