


दीनदयाल पत्तन प्राधिकरण  
DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (TD),  
TD Division,  
Administrative Office Building  
Post Box No. 50, Gandhidham-Kachchh  
[www.deendayalport.gov.in](http://www.deendayalport.gov.in)

\*\*\*\*\*

No: TW/WK/7848-I/

Date:07/12/2024

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Expression of Interest.**

**Sub:- Construction of Kendriya Vidyalaya Building at Port Colony  
Gopalpuri, Gandhidham.**

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary – offer for the items considered in preparation of the estimate under Annexure-I.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before **13/12/2024 by 15:00 Hrs.**

**Address:-**

Office of the Executive Engineer (TD),  
TD Division, Administrative Office Building,  
Ground floor, Room No.103, Annexe,  
P.O. Box No. 50, Gandhidham – Kachchh.

Thanking you,

Yours faithfully,

Sd/-

**Executive Engineer (TD)  
Deendayal Port Authority**

Sr.No.	Description of Items	Unit	Qty	Rate	
1	Providing Texture Painting of approved design on Exterior face of wall including two coat of paint	Sq.mt	2600.00		
2	Providing Buffing work on Kota Stone clading & floor	Sq.mt	1200.00		
3	Providing ridges or hips of width 60cm of GI sheet 0.6 mm thick	Rmt	36.00		
4	Providing & laying PVC louvers on front face ie. sloping portion of hall	Sq.mt	350.00		
5	Providing & fixing sign letter with LED light in front of hall i.e "Sardae vallabh bhai patel Multipurpose Hall" in english & in hindi				
(a)	English & Hindi	Nos	2.00		
(b)	DPT Logo	Nos	1.00		
6	Providing and fixing bright finished brass 200 mm mortice latch and lock, ISI marked, with six levers and a pair of handles of approved quality with necessary screws etc. complete.	Nos	85.00		
7	Inside Wall Paper, Verticle blind curtain etc.	L.S	1.00		
8	Aluminium paint to existing chainlink & fencing	Sq.mt	700.00		
9	Repair to existing Chainlink & fencing	Kg	100.00		
10	Door Frame Peripheri with laminate Sheet	Rm	470.00		
11	Providing & Fixing Decorative Statue	Nos	1.00		
12	Singles for sloping roof	Sq.mt	150.00		
13	Vitrified Tiels Floring & cladding	Sq.mt	900.00		
14	Providing & Fixing wash basin jaquar 500x380x120mm with pillar tap of 15mm dia swan type	Nos	21.00		
15	Supply and Installation Health Faucet	Nos	20.00		
16	12mm thick toughned glass for glazing in front of building including cutout breackets for fixing of glass	Sq.mt	100.00		
17	5mm thick toughned glass for glazing in front of building including cutout breackets for fixing of glass	Sq.mt	140.00		
18	Providing & Fixing WC - Extended wall mounting (780x370x690mm)	Nos	20.00		
19	Modification & strengthening of existing parking shed for installation of solar panel including construction of room.	L.S	1.00		
20	Removing Existing Chair	Nos	700.00		
21	Providing & Fixing HDPE BLOW moulding 4 Sheater joint molded chairs	Nos	500.00		
22	Providing & Fixing 30 mm thick flush door with both face laminate	Sq.mt	120.00		