



DEENDAYAL PORT AUTHORITY



PHONE NO: - 02836-270484/27035

FAX NO: - 02836-270184

WEB : www.deendayalport.gov.in

Email: xenedpa@gmail.com

Electrical Division

NIRMAN BUILDING,

NEW KANDLA (KUTCH)

PIN ODE: 370 210

No. EL/WK/2873

Dated: 11.03.2025

**To,
M/s.**

"EXPRESSION OF INTERSET (EOI)"

Subject: - "Construction of E & D Type Quarters at Gopalpuri-Electric Part".

Sir,

Expression of interest (EOI) are invited to carry out the work ""Construction of E & D Type Quarters at Gopalpuri-Electric Part" as per Technical specification, Terms &, Conditions stipulated below.

The Expression of interest (EOI) along with Schedule-B should reach this office of undersigned on or before 18/03/2025 at 14.00hrs or scanned copy of scanned offer also accepted on e-mail xenedpa@gmail.com which shall be opened on the same day.

Yours faithfully,

Sd/-

Executive Engineer (E)
Deendayal Port Authority

Technical specification

1. Technical Specification No.01

Supply of 4 Meters Octagonal Electric GI Pole conforming to IS 5986 with average thickness of coating not less than 65 Microns as per IS 2629, Thickness of GI Sheet 3 mm, Thickness of Base Plate 12mm, bottom and top diameter of Pole to be 130 mm and 70 mm respectively, GI Pole Base Plate size of 200 mm x 200 mm with minimum slot for adjustment, PCD of SS foundation bolt 200 mm with adjustment slot, and SS bolt diameter of 16mm with GI Base Plate of 200 mm x 200 mm x 12 mm with adjustment slot at concrete surface.

2. Technical Specification No.02

Fixing of Octagonal Pole with required excavation of 0.60 M x 0.60 M x 0.90 M , 0.10 M PCC at Base with RCC Footing/Foundation dimension of 0.45 M Length x 0.45 M Width x 0.80 M Depth with required steel of 12 mm at 100 mm C/C and fixing the GI Base Plate with SS Bolts while Concreting in Line & Level and refilling the same with excavated material, watering and compaction.

3. Technical Specification No.03

Supply & Installation of following type distribution board along with complete with DP, SP MCB and ELCB as per Technical Specification Below.

This includes supply at site 16 way double door SPN DB with IP42 degree of protection. TH DB shall be made from special grade of CRCA sheet and powder coated. The DB shall be fitted with Bus Bar, DIN Rail and neutral link. Along with each DB box, the following MCBs & ELCB shall be supplied and accordingly calculate the quantity. The rates shall be including the cost of MCBs & RCCB supplied along with DB.

1	MCB (C-Curve) 10-16 A Single Pole	7 Nos
2	MCB (C-Curve) 32 A 2 Pole	1 Nos
3	RCCB 30A/32A 4 Pole(100 Milli Ampere Sensitivity)	1 Nos

4. Technical Specification No.04

This includes fixing and commissioning of supplied double door DB on wall /concealed structure as directed. The DB shall be fixed rigidly on wall through suitable size of nut bolts / anchor fasteners / cemented wooden gutties as directed. This includes necessary wiring, connections & earth linking with all material and labour as directed by Engineer-in-Charge.

Sd/-

Executive Engineer (E)
Deendayal Port Authority

Schedule –B

Sub: - "Construction of E & D Type Quarters at Gopalpuri-
Electric Part".

Sr. No.	Description Of work	Qty	Unit	Rate (Rs.)	Amount
				In Fig	
1.	Supply of 4 Meters Octagonal Electric GI Pole conforming to IS 5986 (Single Arm of 45Degree with Bracket and 40 W Street Light LED clear white) As per Technical Specification No.01 & 02				
a	Supply	24	No.		
b	Installation	24	No.		
2.	Supply of 4 Meters Octagonal Electric GI Pole conforming to IS 5986 (Double Arm of 45Degree with Bracket and 40 W Street Light LED clear white) As per Technical Specification No.01 & 02				
a	Supply	8	No.		
b	Installation	8	No.		
3.	Supply & Installation of distribution board along with complete with DP, SP MCB and ELCB as per Technical Specification As per Technical Specification No.3 & 4				
a	Supply	24	No.		
b	Installation	24	No.		
Total					

Net Amount in words _____

Signature & Seal of Contractor

S/d-

Executive Engineer (E)
Deendayal Port Authority

Commercial Conditions

1. Taxes & Duties: GST Extra @ 18% Income Tax & GST will be deducted at applicable rates.
2. Payment Terms: 100% after completion of complete of each job and on submission of Invoice through RTGS.
3. Insurance: at the risk & cost of contractor.
4. Travel, accommodation & local conveyance: Inclusive in the rate quoted above.

Seal & Sign
Of Contractor

Sd/-
Executive Engineer (E)
Deendayal Port Authority